

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: ML-22649	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE LP				9. WELL NAME and NUMBER: NBU 922-32CT	
3. ADDRESS OF OPERATOR: PO BOX 173779 CITY DENVER STATE CO ZIP 80217-3779				PHONE NUMBER: (720) 929-6666	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 809' FNL, 2154' FWL <i>631054X 39.987604</i> AT PROPOSED PRODUCING ZONE: SAME <i>4428410Y -109.464817</i>				10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 54 MILES FROM VERNAL, UTAH				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 32 9S 22E S	
				12. COUNTY: UINTAH	
				13. STATE: UTAH	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 809'		16. NUMBER OF ACRES IN LEASE: 640		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 20'		19. PROPOSED DEPTH: 9,340		20. BOND DESCRIPTION: RLB0005237	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5024.6		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION: 10 DAYS	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12 1/4	9 5/8	J-55	36 LTC	2,350	PREMIUM +2%CaCl	215 SK	1.18 15.60
					20 GAS SODIUM S	100	1018 15.6
7 7/8	4 1/2	1-80	11.6	9,340	PREMIUM LITE II+3%	450	3.38 11.6
					50/50 POZ/G	1470	1.31 14.3

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) RALEEN WHITE TITLE SR. REGULATORY ANALYST

SIGNATURE *Raleen White* DATE 6/3/2008

(This space for State use only)

API NUMBER ASSIGNED: 43-04740133

**Approved by the
Utah Division of
Oil, Gas and Mining**

APPROVAL:
Date: 06-08-08
(See Instructions on Reverse Side)
By: *[Signature]*

RECEIVED
JUN 05 2008
DIV. OF OIL, GAS & MINING


T9S, R22E, S.L.B.&M.

KERR McGEE OIL & GAS ONSHORE LP

Well location, NBU #922-32CT, located as shown in the NE 1/4 NW 1/4 of Section 32, T9S, R22E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION



TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)
 LATITUDE = 39°59'51.22" (39.997561)
 LONGITUDE = 109°27'56.15" (109.465597)
 (NAD 27)
 LATITUDE = 39°59'51.35" (39.997597)
 LONGITUDE = 109°27'53.68" (109.464911)

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 05-23-08	DATE DRAWN: 05-28-08
PARTY T.A. S.K. L.K.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE Kerr McGee Oil & Gas Onshore LP	

**NBU 922-32CT
NENW, SECTION 32, T9S, R22E
UINTAH COUNTY, UTAH
ML-22649**

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. Estimated Tops of Important Geologic Markers:

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	1351'
Birds Nest	1670'
Mahogany	2043'
Wasatch	4580'
Mesaverde	7990'
TD	9340'

2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1351'
Water	Birds Nest	1670'
Water	Mahogany	2043'
Gas	Wasatch	4580'
Gas	Mesaverde	7990'
Water	N/A	
Other Minerals	N/A	

3. Pressure Control Equipment (Schematic Attached)

Please refer to the attached Drilling Program.

4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program.

5. Drilling Fluids Program:

Please refer to the attached Drilling Program.

6. Evaluation Program:

Please refer to the attached Drilling Program.

7. Abnormal Conditions:

Maximum anticipated bottomhole pressure calculated at 9340' TD, approximately equals 5791 psi (calculated at **0.62 psi/foot**).

Maximum anticipated surface pressure equals approximately 3736 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at **0.22** psi/foot).

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.

10. **Other Information:**

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP		DATE	June 3, 2008	
WELL NAME	NBW 922-32CT		TD	9,340'	MD/TVD
FIELD	Natural Buttes	COUNTY	Uintah	STATE	Utah
				ELEVATION	5,025' GL KB 5,040'
SURFACE LOCATION	809' FNL, 2154' FWL			BHL	Straight Hole
NAD 83	Latitude:	39.997561	Longitude:	109.465597	
OBJECTIVE ZONE(S)	Wasatch/Mesaverde				
ADDITIONAL INFO	Regulatory Agencies: BLM (SURF & MINERALS), UDOGM, Tri-County Health Dept.				

GEOLOGICAL FORMATION LOGS			MECHANICAL		
TOPS	DEPTH		HOLE SIZE	CASING SIZE	MUD WEIGHT
	40'			14"	
			12-1/4"	9-5/8", 36#, J-55, LTC	Air mist
Catch water sample, if possible, from 0 to 4,580'					
	Green River @ 1,351'				
	Top of Birds Nest Water @ 1,670'				
	Preset f/ GL @ 2,350' MD				
Note: 12.25" surface hole will usually be drilled ±400' below the bottom of lost circulation zone. Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.					
	Mahogany @ 2,043'				
Mud logging program TBD Open hole logging program f/ TD - surf csg					
	Wasatch @ 4,580'		7-7/8"	4-1/2", 11.6#, I-80 or equivalent LTC casing	Water/Fresh Water Mud 8.3-11.6 ppg
	Mverde @ 7,102'				
	MVU2 @ 7,990'				
	MVL1 @ 8,610'				
	TD @ 9,340'				Max anticipated Mud required 11.6 ppg



KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3520	2020	453000
SURFACE	9-5/8"	0 to 2,350'	36.00	J-55	LTC	0.98	1.84	6.11
						7780	6350	201000
PRODUCTION	4-1/2"	0 to 9340	11.60	I-80	LTC	2.17	1.13	2.13

- 1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))
- 2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)
- (Burst Assumptions: TD = 11.6 ppg) .22 psi/ft = gradient for partially evac wellbore
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)
- MASP 3579 psi

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
	TOP OUT CMT (1)	250	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	100		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2	NOTE: If well will circulate water to surface, option 2 will be utilized						
	LEAD	2000	Prem cmt + 16% Gel + 10 pps gilsonite + .25 pps Flocele + 3% salt BWOC	230	35%	11.60	3.82
	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,080'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	450	60%	11.60	3.38
	TAIL	5,260'	50/50 Poz/G + 10% salt + 2% gel + .1% R-3	1470	60%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney

DATE:



DRILLING SUPERINTENDENT:

Randy Bayne

dhd 922-32CT

DATE:

5M BOP STACK and CHOKE MANIFOLD SYSTEM



NBU 922-32CT
NENW SEC 32-T9S-R22E
Uintah County, UT
ML-22649

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

No new access road is proposed. Refer to Topo Map B for the location of existing access road.

The upgraded portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet. Appropriate water control will be installed to control erosion.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. Location of Existing Wells Within a 1-Mile Radius:

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities:

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or

installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Carlsbad Canyon, standard color number 2.5Y 6/2.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

No new pipeline is proposed for this location.

5. Location and Type of Water Supply:

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. Source of Construction Materials:

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. Methods of Handling Waste Materials:

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner and felt will be used, it will be a minimum of 20 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled By truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E , Pipeline Facility Sec. 36, T9S, R20E, Goat Pasture Evaporation Pond SW/4 Sec. 16, T10S, R22E, Bonanza Evaporation Pond Sec. 2, T10S, R23E

8. Ancillary Facilities:

None are anticipated.

9. Well Site Layout: (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. Plans for Reclamation of the Surface:

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

A plastic, nylon reinforced liner will be used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. Surface and Mineral Ownership:

SITLA
675 East 500 South, Suite 500
Salt Lake City, UT 84102

12. Other Information:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey has been completed and is attached.

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it Within 460' of any non-committed tract lying within the boundaries of the Unit.

13. Lessee's or Operators's Representative & Certification:

Raleen White
Sr. Regulatory Analyst
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6666

Randy Bayne
Drilling Manager
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435)781-7018


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by State Surety Bond #RLB0005236.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Raleen White

Date 6-3-2008

Kerr-McGee Oil & Gas Onshore LP
NBU #922-32CT
SECTION 32, T9S, R22E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 6.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN RIGHT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 3.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 4.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY, THEN NORTHERLY DIRECTION APPROXIMATELY 2.1 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE EXISTING #241 AND THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 54.2 MILES.

Kerr-McGee Oil & Gas Onshore LP

NBU #922-32CT

LOCATED IN UTAH COUNTY, UTAH
SECTION 32, T9S, R22E, S.L.B.&M.




PHOTO: VIEW FROM PIT CORNER C TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY




PHOTO: VIEW OF EXISTING ACCESS

CAMERA ANGLE: NORTHEASTERLY



- Since 1964 -

UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

05 29 08
MONTH DAY YEAR

PHOTO

TAKEN BY: T.A.

DRAWN BY: L.K.

REVISED: 00-00-00


Kerr-McGee Oil & Gas Onshore LP

FIGURE #1

LOCATION LAYOUT FOR

NBU #922-32CT
SECTION 32, T9S, R22E, S.L.B.&M.
809' FNL 2154' FWL


Existing Access Road



SCALE: 1" = 50'
DATE: 05-28-08
Drawn By: L.K.

NOTE:


Flare Pit is to be located a min. of 100' from the Well Head.



NOTES:

FINISHED GRADE ELEV. AT LOC. STAKE = 5024.6'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017



LEGEND:

● PROPOSED LOCATION



Kerr-McGee Oil & Gas Onshore LP

NBU #922-32CT

SECTION 32, T9S, R22E, S.L.B.&M.

809' FNL 2154' FWL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

05 29 08
 MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: L.K. REVISED: 00-00-00





LEGEND:

EXISTING ROAD
 PROPOSED ACCESS ROAD



Kerr-McGee Oil & Gas Onshore LP

NBU #922-32CT

SECTION 32, T9S, R22E, S.L.B.&M.

809' FNL 2154' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**

05 29 08
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: L.K. REVISED: 00-00-00



R
22
E

PROPOSED LOCATION:
NBU #922-32CT

T9S
T10S

LEGEND:

- | | |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS | ○ WATER WELLS |
| ● PRODUCING WELLS | ● ABANDONED WELLS |
| ● SHUT IN WELLS | ● TEMPORARILY ABANDONED |



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



Kerr-McGee Oil & Gas Onshore LP

NBU #922-32CT
SECTION 32, T9S, R22E, S.L.B.&M.
809' FNL 2154' FWL

TOPOGRAPHIC
MAP

05 29 08
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: L.K. REVISED: 00-00-00



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 06/05/2008

API NO. ASSIGNED: 43-047-40133

WELL NAME: NBU 922-32CT
OPERATOR: KERR-MCGEE OIL & GAS (N2995)
CONTACT: RALEEN WHITE

PHONE NUMBER: 720-929-6666

PROPOSED LOCATION:

NENW 32 090S 220E
SURFACE: 0809 FNL 2154 FWL
BOTTOM: 0809 FNL 2154 FWL
COUNTY: UINTAH
LATITUDE: 39.99760 LONGITUDE: -109.4648
UTM SURF EASTINGS: 631054 NORTHINGS: 4428410
FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	DKD	7/16/08
Geology		
Surface		

LEASE TYPE: 3 - State
LEASE NUMBER: ML-22649
SURFACE OWNER: 3 - State

PROPOSED FORMATION: MVRD
COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 22013542)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 43-8496)
☒ RDCC Review (Y/N)
(Date: _____)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)


LOCATION AND SITING:

____ R649-2-3.
Unit: _____
____ R649-3-2. General
Siting: 460' From Qtr/Qtr & 920' Between Wells
____ R649-3-3. Exception
☒ Drilling Unit
Board Cause No: 173-14
Eff Date: 12.2.1999
Siting: 400' to 460' from Uncomm. Tracer
____ R649-3-11. Directional Drill

COMMENTS: Needs Permit (6-19-08)

STIPULATIONS: 1- STATEMENT OF BASIS
2- OIL SHALE
3- Surface Csg Cont stop

CAUSE: 173-14 / 12-2-1999 NATURAL BUTTES UNITNATURAL BUTTES FIELD



OPERATOR: KERR MCGEE O&G (N2995)

SEC: 31,32 T.9S R. 22E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH

CAUSE: 173-14 / 12-2-1999

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHEML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



PREPARED BY: DIANA MASON
DATE: 16-JUNE-2008

Application for Permit to Drill

Statement of Basis

7/3/2008

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Ownr	CBM
814	43-047-40133-00-00		GW	S	No
Operator	KERR-MCGEE OIL & GAS ONSHORE, L.P. Surface Owner-APD				
Well Name	NBU 922-32CT	Unit			
Field	NATURAL BUTTES	Type of Work			
Location	NENW 32 9S 22E S 809 FNL 2154 FWL GPS Coord (UTM) 631054E 4428410N				

Geologic Statement of Basis

Kerr McGee proposes to set 2,350' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 3,500'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The production casing cement should be brought up above the base of the moderately saline ground water in order to isolate it from fresher waters up hole. The proposed casing and cement should adequately protect. Any usable ground water.

Brad Hill

7/3/2008

APD Evaluator

Date / Time

Surface Statement of Basis

The proposed NBU 922-32CT gas well is on the existing location of the CIGE #241 gas well. This well is planned to be plugged. A reserve pit 70' x 140' x 10' deep will be re-dug in the southeast corner of the location. The existing pad appears to be stable and should present no problems for drilling and operating the proposed well.

Floyd Bartlett

6/19/2008

Onsite Evaluator

Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator KERR-MCGEE OIL & GAS ONSHORE, L.P.
Well Name NBU 922-32CT
API Number 43-047-40133-0 **APD No** 814 **Field/Unit** NATURAL BUTTES
Location: 1/4,1/4 NENW **Sec** 32 **Tw** 9S **Rng** 22E 809 FNL 2154 FWL
GPS Coord (UTM) 631049 4428406 **Surface Owner**

Participants

Floyd Bartlett and David Hackford (DOGM), Jim Davis (SITLA), Raleen White, Clay Einerson and Tony Kzneck (Kerr McGee) and David Kay (Uintah Engineering and Land Surveying).

Regional/Local Setting & Topography

The proposed NBU 922-32CT gas well is on the existing location of the CIGE #241 gas well. This well is planned to be plugged. A reserve pit 70' x 140' x 10' deep will be re-dug in the southeast corner of the location. The existing pad appears to be stable and should present no problems for drilling and operating the proposed well.

Surface Use Plan

Current Surface Use

Existing Well Pad

New Road

Miles	Well Pad	Length	Src Const Material	Surface Formation
	Width			

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetland

Flora / Fauna

Soil Type and Characteristics

Erosion Issues

Sedimentation Issues

Site Stability Issues

Drainage Diversion Required

Berm Required?

Erosion Sedimentation Control Required?

Paleo Survey Run?	Paleo Potential Observed?	Cultural Survey Run?	Cultural Resources?
--------------------------	----------------------------------	-----------------------------	----------------------------

Reserve Pit**Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	300 to 1320	10
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0

Final Score 25 1 **Sensitivity Level**

Characteristics / Requirements

A reserve pit 70' x 140' x 10' deep will be re-dug in the southeast corner of the location.


Closed Loop Mud Required? N **Liner Required?** Y **Liner Thickness** 16 **Pit Underlayment Required?** Y

Other Observations / Comments

Floyd Bartlett
Evaluator

6/19/2008
Date / Time

Casing Schematic



Well name:	2008-07 Kerr McGee NBU 922-32CT	
Operator:	Kerr McGee Oil & Gas Onshore L.P.	
String type:	Surface	Project ID: 43-047-40133
Location:	Uintah County, Utah	

Design parameters:
Collapse

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 108 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,300 ft

Cement top: 460 ft

Burst

Max anticipated surface pressure: 2,068 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,350 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 2,060 ft

Completion type is subs
Non-directional string.

Re subsequent strings:

Next setting depth: 9,340 ft
Next mud weight: 11.600 ppg
Next setting BHP: 5,628 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,350 ft
Injection pressure: 2,350 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2350	9.625	36.00	J-55	LT&C	2350	2350	8.796	1020.1

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1017	2020	1.986	2350	3520	1.50	74	453	6.11 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Minerals

Phone: (801) 538-5357
FAX: (801) 359-3940

Date: July 8, 2008
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2350 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes.
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

2008-07 Kerr McGee NBU 922-32CTOperator: **Kerr McGee Oil & Gas Onshore L.P.**String type: **Production**

Project ID:

43-047-40133Location: **Uintah County, Utah****Design parameters:****Collapse**

Mud weight: 11.600 ppg
Internal fluid density: 2.300 ppg

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 206 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 3,573 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 5,628 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Completion type is subs
Non-directional string.

Tension is based on buoyed weight.

Neutral point: 7,720 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft ³)
1	9340	4.5	11.60	I-80	LT&C	9340	9340	3.875	815.1

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4512	6360	1.409	5628	7780	1.38	90	212	2.37 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Minerals

Phone: (801) 538-5357
FAX: (801) 359-3940

Date: July 8, 2008
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9340 ft, a mud weight of 11.6 ppg. An internal gradient of .119 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

BOPE REVIEW

Kerr-McGee NBU 922-32CT API 43-047-40133

INPUT

Well Name

Kerr-McGee NBU 922-32CT API 43-047-40133

Casing Size (")

String 1	String 2		
9 5/8	4 1/2		
2350	9340		
40	2350		
8.4	11.6		
500	5000		
3520	7780		
5791	11.9 ppg		

Setting Depth (TVD)

Previous Shoe Setting Depth (TVD)

Max Mud Weight (ppg)

BOPE Proposed (psi)

Casing Internal Yield (psi)

Operators Max Anticipated Pressure (psi)

Calculations

String 1 9 5/8 "

Max BHP [psi] .052*Setting Depth*MW = 1026

BOPE Adequate For Drilling And Setting Casing at Depth?

MASP (Gas) [psi] Max BHP-(0.12*Setting Depth) = 744

NO Air Drill to surface shoe with diverter

MASP (Gas/Mud) [psi] Max BHP-(0.22*Setting Depth) = 509

*Can Full Expected Pressure Be Held At Previous Shoe?

Pressure At Previous Shoe Max BHP-.22*(Setting Depth - Previous Shoe Depth) = 518

NO Common in Area - no expected pressures

Required Casing/BOPE Test Pressure 2350 psi

*Max Pressure Allowed @ Previous Casing Shoe = 40 psi

*Assumes 1psi/ft frac gradient

Calculations

String 2 4 1/2 "

Max BHP [psi] .052*Setting Depth*MW = 5634

BOPE Adequate For Drilling And Setting Casing at Depth?

MASP (Gas) [psi] Max BHP-(0.12*Setting Depth) = 4513

YES ✓

MASP (Gas/Mud) [psi] Max BHP-(0.22*Setting Depth) = 3579

YES

*Can Full Expected Pressure Be Held At Previous Shoe?

Pressure At Previous Shoe Max BHP-.22*(Setting Depth - Previous Shoe Depth) = 4096

NO Reasonable

Required Casing/BOPE Test Pressure 5000 psi

*Max Pressure Allowed @ Previous Casing Shoe = 2350 psi

*Assumes 1psi/ft frac gradient



June 9, 2008

Utah Division of Oil, Gas & Mining
1594 W. North Temple, STE 1210
Salt Lake City, UT 84114-5801

Attention: Diana Mason

RE: Twin Locations

Dear Diana:

Per our email correspondences on June 6, 2008 Kerr-McGee Oil & Gas Onshore LP is submitting this letter regarding our twin program. We have several wells that plan to twin in the next few years. Our plan is to drill a second well bore to the Mesaverde formation. The currently producing wells are producing from the Wasatch formation and many will be plugged prior to drilling the Mesaverde well. Below is a current list of locations that we plan to drill a twin Mesaverde well.

✓Wissiu 820-36PT	Twin to the Wissiu 36-114	NBU 1022-3FT	Twin to the NBU 286
✓Federal 821-33MT	Twin to the Federal 33-93	NBU 1022-5BT	Twin to the NBU 140
NBU 920-15FT	Twin to the CIGE 22	NBU 1022-5IT	Twin to the NBU 338
NBU 921-26IT	Twin to the NBU 68-N2	NBU 1022-8IT	Twin to the CIGE 250
NBU 921-30FT	Twin to the NBU 261	NBU 1022-9AT	Twin to the NBU 291
NBU 921-31BT	Twin to the NBU 378	NBU 1022-10HT	Twin to the NBU 293
NBU 921-35AT	Twin to the CIGE 54D	NBU 1022-10FT	Twin to the NBU 248
NBU 922-31CT	Twin to the NBU 354	✓NBU 921-03BT	Twin to SHOYO 3-162
✓NBU 922-31GT	Twin to the CIGE 220	✓NBU 921-20IT	Twin to CIGE 70
NBU 922-32O1T	Twin to the NBU 404	NBU 921-27MT	Twin to NBU 395
NBU 922-32F3T	Twin to the CIGE 106D	NBU 921-27OT	Twin to NBU 305
NBU 922-35IT	Twin to the CIGE 118	✓NBU 921-15MT	Twin to NBU 191
NBU 922-36NT	Twin to the CIGE 147	NBU 921-27HT	Twin to NBU 109
✓NBU 1022-1CT	Twin to the CIGE 105D	NBU 921-27KT	Twin to NBU 83J
NBU 921-27LT	Twin to NBU 214		

RECEIVED

JUN 11 2008



NBU 1022-4N4T	Twin to NBU 148
NBU 922-31L4T	Twin to NBU 41J
NBU 1022-4L1T	Twin to NBU 147
NBU 1022-9F4T	Twin to NBU 150
NBU 1022-4P1T	Twin to NBU 208
NBU 1022-9D1T	Twin to NBU 151
NBU 1022-3G3T	Twin to NBU 185
NBU 1022-10A2T	Twin to NBU 117
NBU 921-11B3T	Twin to NBU 195
NBU 921-21E4T	Twin to NBU 127
NBU 921-8A4T	Twin to NBU 202

The above lists of well locations are planned for the 2008-2009 drilling program. This list may vary depending on the program. Please do not hesitate to call me if you have any further questions or need additional information.

Thank you,

A handwritten signature in cursive script that reads 'Raleen White'.

Raleen White
Sr. Regulatory Analyst

Cc: SITLA – Ed Bonner
BLM Vernal Office – Verlyn Pindell

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

June 16, 2008

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2008 Plan of Development Natural Buttes Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2008 within the Natural Buttes Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ MesaVerde)		
43-047-40136	NBU 921-20IT Sec 20 T09S R21E 1902 FSL 0822 FEL	
43-047-40135	NBU 921-15MT Sec 15 T09S R21E 0697 FSL 0406 FWL	
43-047-40134	NBU 922-31GT Sec 31 T09S R22E 1664 FNL 1349 FEL	
43-047-40133	NBU 922-32CT Sec 32 T09S R22E 0809 FNL 2154 FWL	
(Proposed PZ Wasatch/MesaVerde)		
43-047-40129	NBU 1022-24B1AS Sec 24 T10S R22E 1052 FNL 1583 FEL	
	BHL Sec 24 T10S R22E 0150 FNL 1375 FEL	
43-047-40130	NBU 1022-24B1DS Sec 24 T10S R22E 1026 FNL 1637 FEL	
	BHL Sec 24 T10S R22E 0540 FNL 1605 FEL	
43-047-40131	NBU 1022-24G1S Sec 24 T10S R22E 1044 FNL 1601 FEL	
	BHL Sec 24 T10S R22E 1515 FNL 1580 FEL	
43-047-40141	NBU 1022-24I1S Sec 24 T10S R22E 2062 FSL 1130 FEL	
	BHL Sec 24 T10S R22E 2330 FSL 0585 FEL	
43-047-40142	NBU 1022-24G3S Sec 24 T10S R22E 2037 FSL 1184 FEL	
	BHL Sec 24 T10S R22E 2225 FNL 2140 FEL	
43-047-40140	NBU 1022-24G2S Sec 24 T10S R22E 2053 FSL 1148 FEL	
	BHL Sec 24 T10S R22E 1815 FNL 2100 FEL	

Our records indicate the 1022-24B1AS, 1022-24B1DS, 1022-24G1S and the 1022-24I1 bottom hole location is closer than 460 feet from the Natural Buttes Unit boundary.

We have no objections to permitting the wells so long as the unit operator receives an exception to the locating and siting requirements of the State of Utah (R649-3-2).

/s/ Michael L. Coulthard

bcc: File - Natural Buttes Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:6-16-08

From: Jim Davis
To: Bonner, Ed; Mason, Diana; Raleen.White@anadarko.com
Date: 9/4/2008 4:26 PM
Subject: Fwd: Kerr-McGee Wells

The following wells have been approved by SITLA including PALEO and arch clearance.

4304740133	NBU 922-32CT	Kerr-McGee Oil & Gas	Natural Buttes	NENW	32	090S	220E
S	UINTAH						
4304740134	NBU 922-31GT	Kerr-McGee Oil & Gas	Natural Buttes	SWNE	31	090S	220E
S	UINTAH						

-Jim

Jim Davis
Utah Trust Lands Administration
jimdavis1@utah.gov
Phone: (801) 538-5156

>>> Kristine Curry 9/4/2008 3:41 PM >>>
The following wells have been cleared for cultural resources:

Kerr-McGee's NBU #922-32CT [API #4304740133] (U-08-MQ-0461b,i,p,s)

Kerr-McGee's NBU #922-31GT [API #4304740134] (U-08-MQ-0461b,i,p,s)

I've updated the BS for both of these.

Kristine



JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

September 8, 2008

Kerr-McGee Oil & Gas Onshore, LP
P O Box 173779
Denver, CO 80217-3779

Re: NBU 922-32CT Well, 809' FNL, 2154' FWL, NE NW, Sec. 32, T. 9 South, R. 22 East,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-40133.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
SITLA

Operator: Kerr-McGee Oil & Gas Onshore, LP
Well Name & Number NBU 922-32CT
API Number: 43-047-40133
Lease: ML-22649

Location: NE NW **Sec.** 32 **T.** 9 South **R.** 22 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office (801) 942-0871 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office (801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
7. Surface casing shall be cemented to the surface.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22649
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 922-32CT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 809'FNL, 2154'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 32 9S, 22E		9. API NUMBER: 4304740133
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: WELL SPUD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX.

SPUD WELL LOCATION ON 12/02/2008 AT 0900 HRS.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 12/3/2008

(This space for State use only)

RECEIVED

DEC 08 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22649
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 809'FNL, 2154'FWL		8. WELL NAME and NUMBER: NBU 922-32CT
COUNTY: UINTAH		9. API NUMBER: 4304740133
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 32 9S, 22E		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SET SURFACE CSG
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PROPETRO AIR RIG ON 12/18/2008. DRILLED 12 1/4" SURFACE HOLE TO 2420'. RAN 9 5/8" 36# J-55 SURFACE CSG. CMT W/300 SX PREM CLASS G @15.8 PPG 1.15 YIELD. NO RETURNS THROUGH OUT JOB 400 +/- PSI LIFT. TOP OUT W/100 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE WOC. 2ND TOP OUT W/200 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE GOOD CMT TO SURFACE AND FELL BACK. 3RD TOP OUT W/100 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE GOOD CMT TO SURFACE HOLE STAYED FULL.

WORT

RECEIVED
DEC 31 2008
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 12/29/2008

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22649
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 809'FNL, 2154'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 32 9S, 22E		8. WELL NAME and NUMBER: NBU 922-32CT
PHONE NUMBER: (435) 781-7024		9. API NUMBER: 4304740133
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: FINAL DRILLING OPERATIONS
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

FINISHED DRILLING FROM 2420' TO 9275' ON 01/11/2009. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/400 SX PREM LITE II @11.7 PPG 2.60 YIELD. TAILED CMT W/1250 SX 50/50 POZ @14.3 PPG 1.31 YIELD. WASH LINES DROP PLUG & DISPLACE W/143.3 BBLs WATER CLAY TREATED + 1 GAL MAGNACIDE @8.3 PPG BUMP PLUG W/3413 PSI PLUG HELD 2740 PUMPING PSI 673 OVER PSI LOST DISPLACEMENT 120 BBLs INTO DISPLACEMENT 1.5 BBL BLEED OFF ATTEMPT TO SET MANDREL PACKING ASSEMBLY #1 ASSEMBLY PULLED OUT AFTER LOCK DOWN REINSTALL PACKING ASSEMBLY #2 LOCK DOWN & TEST TO 5000 PSI. NIPPLE DOWN BOP CHLORINE TABS DOWN CSG INSTALL NIGHT CAP & CLEAN MUD PITS.

RELEASED PIONEER TIG 68 ON 01/13/2009 AT 1600 HRS.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 1/13/2009

(This space for State use only)

RECEIVED
JAN 20 2009
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22649
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 809'FNL, 2154'FWL		8. WELL NAME and NUMBER: NBU 922-32CT
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 32 9S, 22E		9. API NUMBER: 4304740133
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: PRODUCTION START-UP
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE SUBJECT WELL WAS PLACED ON PRODUCTION ON 02/20/2009 AT 10:00 AM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 2/24/2009

(This space for State use only)

RECEIVED
MAR 02 2009

ROCKIES

Operation Summary Report

Well: NBU 922-32CT			Spud Conductor: 12/2/2008				Spud Date: 12/18/2008	
Project: UTAH			Site: UINTAH				Rig Name No: PROPETRO/, PIONEER 68/68	
Event: DRILLING			Start Date: 12/2/2008				End Date: 1/13/2009	
Active Datum: RKB @5,043.00ft (above Mean Sea Level)			UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation
12/18/2008	19:00 - 0:00	5.00	DRLSUR	02		P		DRILL F/ 40' TO 270'
12/19/2008	0:00 - 12:00	12.00	DRLSUR	02	A	P		DRILL F/ 270' TO 810'
	12:00 - 0:00	12.00	DRLSUR	02	A	P		DRILL F/ 810' TO 1130'
12/20/2008	0:00 - 12:00	12.00	DRLSUR	02	A	P		DRILL F/ 1130' TO 1260' TFNB.
	12:00 - 0:00	12.00	DRLSUR	02	A	P		DRILL F/ 1260' TO 1600' CIRC W/ RIG PUMP.
12/21/2008	0:00 - 12:00	12.00	DRLSUR	02	A	P		DRILL F/ 1600' TO 1730' CIRC W/ SKID PUMP
	12:00 - 0:00	12.00	DRLSUR	02	A	P		DRILL F/ 1730' TO 1980' CIRC W/ SKID PUMP
12/22/2008	0:00 - 12:00	12.00	DRLSUR	02		P		SURVEY 1/2 DEGREE
	12:00 - 21:00	9.00	DRLSUR	02		P		RIG DRILLING AHEAD CIRCULATING WITH SKID PUMP 2220'
	21:00 - 0:00	3.00	DRLSUR	05		P		RIG T/D @ 2420' CONDITION HOLE 1 HR RUN
12/23/2008	0:00 - 1:30	1.50	DRLSUR	05		P		SURVEY 1 DEG.
	1:30 - 5:30	4.00	DRLSUR	11		P		TRIP DP OUT OF HOLE
	5:30 - 6:30	1.00	DRLSUR	15		P		FINISH TRIPPING DP OUT OF HOLE
	6:30 - 7:00	0.50	DRLSUR	15		P		RUN 2337' OF 9 5/8 CSG WAS UNABLE TO RUN
	7:00 - 14:00	7.00	DRLSUR	15		P		LAST JNT LAY JNT DOWN AND LAND CSG RIG
	14:00 - 15:00	1.00	DRLSUR	15		P		DOWN AIR RIG
	15:00 - 15:00	0.00	DRLSUR					CEMENT 1ST STAGE WITH 300 SKS TAIL @ 15.8#
12/30/2008	12:00 - 0:00	12.00	RDMO	01	E	P		1.15 5.0 GAL/SK NO RETURNS THRUOUT JOB + -
12/31/2008	0:00 - 7:00	7.00	RDMO	01	E	P		400 PSI LIFT
	7:00 - 14:00	7.00	RDMO	01	A	P		1ST TOP JOB 150 SKS DOWN BS WOC
	14:00 - 18:00	4.00	MIRU	01	B	P		2ND TOP JOB 200 SKS DOWN BS GOOD CMT TO
	18:00 - 0:00	6.00	MIRU	01	B	P		SURFACE AND FELL BACK WOC
1/1/2009	0:00 - 7:00	7.00	MIRU	01	B	P		3RD TOP JOB 100 SKS DOWN BS GOOD CMT TO
	7:00 - 13:00	6.00	MIRU	01	A	P		SURFACE AND STAYED AT SURFACE
	13:00 - 0:00	11.00	MIRU	01	B	P		NO VISIBLE LEAKS PIT 55% FULL WORT
								RIG DOWN ON THE NBU 922-34D-3 AND GET
								READY FOR TRUCKS.
								RIG DOWN RIG AND READY FOR TRUCKS.
								HOLD SAFETY MEETING W/ L & S TRUCKING AND
								J C CRANES SERVICE. (5 HUAL TRUCKS AND 3
								BED TRUCKS, 4 SWAMPERS AND 2 FORKLIFTS.)(
								1 JC CRANE W/ 3 SWAMPERS) (11 PIONEER
								HANDS.) MOVE RIG OUT EXCEPT CAMPS AND
								PIPE TUBS. MUD TRAILER, AND MUD TANKS.
								SET IN SUB, STEEL PITS, PUMPS, CARRIER,
								LIGHT PLANT, GAS BUSTER, DIESEL TANK,
								BOILER. STAND DOWN TRUCKS AND CRANE
								FOR NIGHT.
								HALF MASS DERRICK AND RAISE SUB. RIG UP
								RIG. RIG 50% RIGGED UP.
								RIG UP BACK YARD.
								FINSIH RIG UP W/ CRANE, RELEASE CRANE
								10:00 A.M. SET WATER TANKS,
								ACCUMMALATOR HOUSE, CAMPS AND PIPE
								TUBS, RELEASE TRUCK 13:00 (3 HUAL TRUCKS
								AND 2 BED TRUCKS.) RELEASE MOUNTAIN
								WEST HANDS 13:00
								RIG UP RIG, RIG 100% RIGGED UP, START
								NIPPLE UP.

ROCKIES

Operation Summary Report

Well: NBU 922-32CT			Spud Conductor: 12/2/2008				Spud Date: 12/18/2008	
Project: UTAH			Site: UINTAH				Rig Name No: PROPETRO/, PIONEER 68/68	
Event: DRILLING			Start Date: 12/2/2008				End Date: 1/13/2009	
Active Datum: RKB @5,043.00ft (above Mean Sea Level)			UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation
1/2/2009	0:00 - 6:00	6.00	DRLPRO	13	A	P		LOCK DOWN FMC LOCKDOWN FLANGE AND SPOOL AND TEST TO 5000 PSI FOR 10 MIN, NIPPLE UP BOP'S, CHOKE LINE, INSTALL ROT HEAD AND FLOWLINE. INSTALL HYDRALIC LINES AND FUNCTION TEST.
	6:00 - 11:30	5.50	DRLPRO	13	C	P		PRESSURE TEST BOP EQUIPMENT TO 5000 PSI FOR 10 MIN AND 250 PSI FOR 5 MIN. TEST ANNULAR TO 2500 PSI FOR 10 MIN AND 250 PSI FOR 5 MIN. TEST CSG TO 1500 PSI FOR 30 MIN. INSTALL WEAR BUSHING.
	11:30 - 13:30	2.00	DRLPRO	17		P		DO PRE SPUD INSPECTION. PRIME PUMPS, HOLD SAFETY MEETING, WASH OUT MOUSE HOLE TO INSTALL MOUSE HOLE SOCK.
	13:30 - 18:00	4.50	DRLPRO	05	A	P		HOLD SAFETY MEETING W/ WEATHERFORD TRS, RIG UP LAYDOWN TRUCK AND P/U BHA AND DRILL STRING, RIG DOWN LAYDOWN TRUCK.
	18:00 - 21:00	3.00	DRLPRO	06	D	P		HOLD JSA, SLIP AND CUT DRILL LINE. RIG SERVICE.
	21:00 - 23:00	2.00	DRLPRO	13	B	P		INSTALL ROT. HEAD RUBBER, TOUQUE KELLY, TIGHTEN DRESSER SLEEVES FOR FLOW LINE, CHECK GAS BUSTER, CHANGE OUT FLOWLINE SENSORS.
1/3/2009	23:00 - 0:00	1.00	DRLPRO	02	F	P		DRILL CEMENT FROM 2240'.
	0:00 - 2:30	2.50	DRLPRO	02	F	P		DRILL CEMENT F/ 2240' TO 2438' (FLOAT @ 2309', SHOE 2359'.
	2:30 - 9:00	6.50	DRLPRO	02	B	P		ROT. SPUD 2/3/2009 02:30 DRILL F/ 2438' TO 3029' (591', 91'/HR)
	9:00 - 9:30	0.50	DRLPRO	09	B	P		SURVEY W/ WIRELINE MULTISHOT TOOL. 2954'=.8 DEGREES , AZMITH 177.3
	9:30 - 14:30	5.00	DRLPRO	02	B	P		DRILL F/ 3029' TO 3472' (443', 89'/HR)
	14:30 - 21:00	6.50	DRLPRO	02	B	P		DRILL F/ 3472' TO 4041' (569', 88'/HR) MUD WT 8.9 VIS 32
	14:30 - 14:30	0.00	DRLPRO	06	A	P		RIG SERVICE. FUNCTION BOP'S.
	21:00 - 21:30	0.50	DRLPRO	09	B	P		SURVEY WITH MAGNETIC WIRELINE TOOL 3966' = 2.7 DEGREES AZI = 154.2
1/4/2009	21:30 - 0:00	2.50	DRLPRO	02	B	P		DRILL F/ 4041' TO 4305' (264', 105'/HR) MUD WT 9.1 VIS 33
	0:00 - 8:00	8.00	DRLPRO	02	B	P		DRILL F/ 4305' TO 5085' (780',97.5'/HR) MUD WT 9.5 VIS 34
	8:00 - 9:00	1.00	DRLPRO	09	B	P		WIRELINE MAGNETIC SURVEY 5010'= 2.2 DEGREES AZI = 157.2
	9:00 - 10:30	1.50	DRLPRO	02	B	P		DRILL F/ 5085' TO 5188' MUD WT 9.6 VIS 34
	10:30 - 12:00	1.50	DRLPRO	04	D	X		LOSS ALL CIRC 5188'. MIXED 30% LCM PILL AND INCREASE LCM TO 6%. REGAINED CIRC. SOME SEEPAGE INCREASE LCM TO 8%. RECIEVED 340 BBLs OF 10.6 WT 4% LCM MUD FROM PIONEER 54. (LOSS 150 BBLs TOTAL)
	12:00 - 13:30	1.50	DRLPRO	07	B	Z		PROBLEMS W/ #2 PUMP DUE TO LCM, WHILE REPAIRING CHARGE PUMP #1, WORK ON PUMPS (CIRC. W/ REDUCED STROKES ON #2)
	13:30 - 0:00	10.50	DRLPRO	02	B	P		DRILL F/ 5188' TO 5936' (748', 71'/HR) MUD WT 10 VIS 38, INCREASED LCM TO 12% DUE TO CONTINUED SEEPAGE. LOSSES CONTAINED @ REPORT TIME
1/5/2009	0:00 - 2:30	2.50	DRLPRO	02	B	P		DRILL F/ 5936' TO 6098' (162',65'/HR) MUD WT 10 VIS 37
	2:30 - 3:30	1.00	DRLPRO	09	B	P		WIRELINE MAGNETIC SURVEY 6023= 2.2 DEGREES AZI= 155.8
	3:30 - 6:00	2.50	DRLPRO	02	B	P		DRILL F 6098' TO 6224' (126', 50.4'/HR) MUD WT 10+ VIS 38. LOSS ALL CIRC. (LOSS 100 BBLs)

ROCKIES

Operation Summary Report

Well: NBU 922-32CT			Spud Conductor: 12/2/2008				Spud Date: 12/18/2008		
Project: UTAH			Site: UINTAH				Rig Name No: PROPETRO/, PIONEER 68/68		
Event: DRILLING			Start Date: 12/2/2008				End Date: 1/13/2009		
Active Datum: RKB @5,043.00ft (above Mean Sea Level)			UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation	
1/6/2009	6:00 - 8:00	2.00	DRLPRO	04	D	P		LOST CIRC. STOP CIRC. MIX 30% LCM PILL AND PUMP DOWN HOLE, RAISE LCM TO 20% THROUGHOUT SYSTEM, REGAIN FULL CIRC.	
	8:00 - 10:30	2.50	DRLPRO	07	B	Z		WORK ON PUMPS, CHANGE 5 SEATS #2 PUMP. #1 PUMP PROBLEM W/ PRESSURE.	
	10:30 - 11:00	0.50	DRLPRO	06	A	P		RIG SERVICE. FUCNTION BOP'S	
	11:00 - 0:00	13.00	DRLPRO	02	B	P		DRILL F/ 6224' TO 6816' (592', 53'/HR) MUD WT 10.5 VIS 40 LCM 19%, NO LOSSES @ THIS TIME.	
	0:00 - 13:30	13.50	DRLPRO	02	B	P		DRILL F/ 6816' TO 7363' 547' TOTAL @ 40.5' HR	
	13:30 - 14:00	0.50	DRLPRO	06	A	P		RIG SERVICE	
	14:00 - 17:30	3.50	DRLPRO	02	B	P		DRILL F/ 7363' - 7458' 95' TOTAL @ 27.1' HR 42 VIS 11.7+ MW 19% LCM	
	17:30 - 18:00	0.50	DRLPRO	04	A	P		HOLE TAKING FLUID LOST 74 BBLS,RAISE LCM TO 22%	
1/7/2009	18:00 - 0:00	6.00	DRLPRO	02	B	P		DRILL F/ 7458' - 7690' 232' TOTAL @ 38.6' HR 40 VIS 10.7 MW 22% LCM. NO MORE MUD LOSS.	
	0:00 - 14:00	14.00	DRLPRO	02	B	P		DRILL F/ 7690' - 8249' 559' TOTAL @ 39.9' HR WILDCAT AUTO DRILLER DOWN.	
	14:00 - 14:30	0.50	DRLPRO	13	D	S		2" BOP DRAIN VALVE LEAKING MUD.	
	14:30 - 15:00	0.50	DRLPRO	06	A	P		RIG SERVICE	
	15:00 - 15:30	0.50	DRLPRO	07	A	S		LIGHT PLANTS DOWN	
	15:30 - 16:30	1.00	DRLPRO	02	B	P		DRILL F/ 8249' - 8270' 21' TOTAL @ 21' HR. 2900 PSI & BLEW POP OFF W/ 105 SPM	
	16:30 - 18:00	1.50	DRLPRO	04	C	P		CIRCULATE,MIX & PUMP PILL.DROP SURVEY	
	18:00 - 0:00	6.00	DRLPRO	05	A	P		(HELD SAFETY MEETING) TOOH F/ BIT # 1,WORK TIGHT HOLE W/ JARS @ 4600'	
1/8/2009	0:00 - 4:30	4.50	DRLPRO	05	A	P		LAYDOWN NMDC & IBS,3 PLUGED JETS IN MI616 MOTOR OK!	
	4:30 - 5:00	0.50	DRLPRO	03	A	P		(HELD SAFETY MEETING) MAKE UP NEW BIT & TIH TO 4600'	
	5:00 - 7:30	2.50	DRLPRO	05	A	P		WASH & REAM TIGHT SPOT F/ 4600' - 4618'	
	7:30 - 8:00	0.50	DRLPRO	04	A	P		TIH W/ BIT # 2 KELLY UP & WORK TIGHT SPOT 42' OFF BOTTOM	
	8:00 - 8:30	0.50	DRLPRO	03	E	P		CIRCULATE & REPAIR AUTOMATIC DRILLER	
	8:30 - 9:00	0.50	DRLPRO	06	A	P		WASH & REAM TO BOTTOM 15' FILL	
	9:00 - 20:00	11.00	DRLPRO	02	B	P		RIG SERVICE & REPAIR AIR COMPRESSOR AIR LINE.	
	20:00 - 21:30	1.50	DRLPRO	04	C	P		DRILL F/ 8270' - 8650' 380' TOTAL @ 34.5' HR 41 VIS / 11.8 MW / 20% LCM	
1/9/2009	21:30 - 0:00	2.50	DRLPRO	05	A	P		CIRCULATE MIX & PUMP PILL	
	0:00 - 5:00	5.00	DRLPRO	05	A	P		(HELD SAFETY MEETING) TOOH,WET TRIP 1/2 WAY OUT OF HOLE.	
	5:00 - 12:00	7.00	DRLPRO	05	A	P		TOOH, MOTOR FAILER. WET TRIP 1/2 WAY OUT	
	12:00 - 12:30	0.50	DRLPRO	03	E	P		HELD SAFETY MEETING) SWITCH MOTORS & BIT,TIH	
	12:30 - 16:00	3.50	DRLPRO	02	B	P		WASH & REAM 15' TO BOTTOM, NO FILL.	
	16:00 - 17:00	1.00	DRLPRO	06	D	S		DRILL F/ 8653' TO 8748' 95' TOTAL @ 27.1' HR	
	17:00 - 23:00	6.00	DRLPRO	06	A	P		BAD SPOT FOUND ON DRILL LINE ON DRUM,SLIP & CUT DRLG LINE. CIRCULATING HOLE W/ SWEDGE	
	23:00 - 0:00	1.00	DRLPRO	04	C	P		DRILLF/ 8748' - 8840' 92' TOTAL @ 15.3' HR 42 VIS 12.2 MW / 19% LCM	
1/10/2009	0:00 - 7:30	7.50	DRLPRO	05	A	P		CIRCULATE F/ TOOH	
	7:30 - 9:30	2.00	DRLPRO	05	A	P		(HELD SAFETY MEETING) TOOH,LAYDOWN MOTOR & BIT	
								MAKE UP NEW BIT & TIH TO SHOE. NO JET NOZELS IN BIT	

ROCKIES

Operation Summary Report

Well: NBU 922-32CT			Spud Conductor: 12/2/2008			Spud Date: 12/18/2008		
Project: UTAH			Site: UINTAH			Rig Name No: PROPETRO/, PIONEER 68/68		
Event: DRILLING			Start Date: 12/2/2008			End Date: 1/13/2009		
Active Datum: RKB @5,043.00ft (above Mean Sea Level)			UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation
1/11/2009	9:30 - 13:00	3.50	DRLPRO	04	A	P		TRANSFER MUD TO 400 UPRIGHTS OUT OF SUCTION PIT & CLEAN OUT EXCESSIVE SHALE & ROCK BUILD UP,TRANSFER MUD BACK TO SUCTION PIT.
	13:00 - 18:00	5.00	DRLPRO	05	A	P		TIH W/ BIT # 4
	18:00 - 18:30	0.50	DRLPRO	04	A	P		HOLE TAKING FLUID,CIRCULATE,MIX LCM & BUILD VOLUME
	18:30 - 0:00	5.50	DRLPRO	02	A	P		DRILL F/ 8843' - 8904' 61' TOTAL @ 11.0' HR
	0:00 - 9:00	9.00	DRLPRO	02	A	P		DRILL F/ 8904' - 9033' 129' TOTAL @ 14.3' HR
	9:00 - 9:30	0.50	DRLPRO	06	A	P		RIG SERVICE
	9:30 - 20:30	11.00	DRLPRO	02	A	P		DRILL F/ 9033' - 9275' TD 242' TOTAL @ 22.0' HR
	20:30 - 22:00	1.50	DRLPRO	04	C	P		42 VIS / 12.2 MW / 20% LCM
1/12/2009	22:00 - 23:00	1.00	DRLPRO	05	E	P		CIRCULATE F/ SHORT TRIP
	23:00 - 0:00	1.00	DRLPRO	04	C	P		SHORT TRIP 10 STDS TO 8612'
	0:00 - 1:00	1.00	DRLPRO	04	C	P		CIRCULATE TO LDDS
	1:00 - 13:00	12.00	DRLPRO	05	B	P		CIRCULATE TO LDDS
	13:00 - 18:00	5.00	DRLPRO	08	F	P		(HELD SAFETY MEETING) LDDS,BREAK DOWN KELLY,LD BHA. RIG DOWN WEATHERFORD.
1/13/2009	18:00 - 19:30	1.50	DRLPRO	11	A	P		(HELD SAFETY MEETING) RIG UP
	19:30 - 0:00	4.50	DRLPRO	11	B	P		HALLIBURTON & RUN TRIPLE COMBO F/ 9287' TO SHOE & GR TO SURFACE.RIG DOWN
	0:00 - 3:00	3.00	DRLPRO	11	B	P		(HELD SAFETY MEETING) RIG UP
	3:00 - 5:00	2.00	DRLPRO	04	E	P		WEATHERFORD CSG CREW
	5:00 - 11:00	6.00	DRLPRO	15	A	P		RUN 4.5 PRODUCTION CSG,FILL CSG & CIRC EVERY 40 JTS BECAUSE OF LCM.
	11:00 - 16:00	5.00	DRLPRO	13	A	P		RUN 4.5 PRODUCTION CSG TAG @ 9287' PICK UP FLUTED MANDREL & LAND CASING
								CIRCULATE OUT GAS & RIG DOWN WEATHERFORD.
								(HELD SAFETY MEETING) & RIG UP BJ. SWITCH LINE & TEST TO 4500 PSI. (PUMP 20 BBLS MUD CLEAN @ 8.3 PPG) (PUMP 30 BBLS SCAVENGER 20 SCKS PREMIUN LITE 11 @ 9.5 PPG,8.35 cF SACK YIELD) (PUMP 185 BBLS LEAD 400 SCKS PREMIUM LITE 11 @ 11.7 PPG,2.60cF SACK YIELD) (PUMP 292 BBLS TAIL 1250 SCKS 50:50 POZ MIX @ 14.3 PPG,1.31 cF SACK YIELD) (WASH LINES DROP PLUG & DISPLACE W/ 143.3 BBLS WATER CLAYTREATED + 1 GL MAGNACIDE @ 8.3 PPG) (BUMP PLIUG W/ 3413 PSI,PLUG HELD) (2740 PUMPING PSI) (673 OVER PSI) (LOST DISPLACEMENT 120 BBLS INTO DISPLACEMENT) (1.5 BBLS BLEED OFF) (RIG DOWN BJ & ATTEMPT TO SET MANDREL PACKING ASSEMBLY # 1 ASSEMBLY PULLED OUT AFTER LOCK DOWN. REINSTALL PACKING ASSEMBLY # 2 LOCK DOWN & TEST TO 5000 PSI.
								NIPPLE DOWN BOP,DROP CHLORINE TABS DOWN CSG,INSTALL NIGHT CAP & CLEAN MUD PITS. RELEASE RIG @ 16:00 01/13/2008

ROCKIES

Operation Summary Report

Well: NBU 922-32CT			Spud Conductor: 12/2/2008				Spud Date: 12/18/2008			
Project: UTAH			Site: UINTAH					Rig Name No: KEY 243/243		
Event: COMPLETION			Start Date: 2/12/2009					End Date:		
Active Datum: RKB @5,043.00ft (above Mean Sea Level)				UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation		
2/12/2009	7:00 - 7:15	0.25	COMP	48		P		HSM, REVIEW R/D & R/U		
	7:15 - 16:30	9.25	COMP	47	A	P		ROAD RIG FROM NBU 922-34D3 TO NBU 922-32CT, MIRU, SPOT EQUIP, TALLEY & P/U 150 JNTS 2-3/8 J-55 TBG, L/D 3 JNTS SWIFN.		
2/13/2009	7:00 - 7:15	0.25	COMP	48	B	P		HSM, REVIEW P/U TBG		
	7:15 - 7:15	0.00	COMP	47	B	P		OPEN WELL CONTINUE TO RIH TO 7300', POOH STNDG BACK, N/D BOPS, N/U FRAC VALVES, MIRU B&C TESTERS, P/T FRAC VALVES & CSG VALVES TO 7500#, [GOOD TEST]. MIRU CUTTERS WIRE LINE, P/U RIH W/ 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90° PH, 9140'-9146' 24 HOLES, 9114'-9118 16 HOLES [40 HOLES] SWI. PREP TO FRAC.		
2/16/2009	7:00 - 7:15	0.25	COMP	48		P		HSM, WORKING W/ WIRE LINE		

ROCKIES

Operation Summary Report

Well: NBU 922-32CT		Spud Conductor: 12/2/2008		Spud Date: 12/18/2008	
Project: UTAH		Site: UINTAH			Rig Name No: KEY 243/243
Event: COMPLETION		Start Date: 2/12/2009		End Date:	
Active Datum: RKB @5,043.00ft (above Mean Sea Level)		UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation
	7:15 - 17:00	9.75	COMP	36	E	P		<p>MIRU CUTTERS WIRE LINE & WEATHERFORD FRAC, P/T SURFACE LINES TO 8500#.</p> <p>STG #1] 8:30 OPEN WELL WHP=1300#, BRK DN PERFS @ 3555#, INJT PSI=5050#, INJT RT=50.8, ISIP=2785#, FG=.75, PUMP'D 2147.2 BBLS SLK WTR W/ 80518# SAND W/ 4738# RESIN COAT IN TAIL, ISIP=2792#, FG=.75, AR=50.9, AP=4656#, MR=52.9, MP=6829#, NPI=7#, 40/40 CALC PERFS OPEN.</p> <p>STG #2] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 9000', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90* PH, 8962'-8970' 32 HOLES, 8832'-8834' 8 HOLES [40 HOLES].</p> <p>WHP=1200#, BRK DN PERFS @ 3510#, INJT PSI=6110#, INJT RT=50.4, ISIP=2335#, FG=.71, PUMP'D 1035.9 BBLS W/ 37681# SAND W/ 5048# RESIN COAT IN TAIL, ISIP=2843#, FG=.76, AR=50.8, AP=4842#, MR=51.4, MP=6688#, NPI=504, 25/40 CALC PERFS OPEN.</p> <p>STG#3] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 8766', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90* PH, 8730'-8736', 24 HOLES, 8702'-8706' 16 HOLES [40 HOLES]</p> <p>WHP=830#, INJT PSI=5550#, INJT RT=50.7, ISIP=2477#, FG=.73, PUMP'D 1652.5 BBLS SLK WTR W/ 58903# SAND W/ 5059# RESIN COAT IN TAIL, ISIP=3008#, FG=.79, AR=50.8, AP=481#, MR=51.4, MP=7892#, NPI=531#, 25/40 CALC PERFS OPEN. [NOTE 16 BBLS LEFT IN FLUSH SCREENED OFF, FLOWED WELL BACK & REFLUSHED]</p> <p>STG #4] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 8646', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90* PH, 8608'-8616' 32 HOLES, 8522'-8524' 8 HOLES [40 HOLES]</p> <p>WHP=2460#, INJT PSI=6000#, INJT RT=50.8, ISIP=2496#, FG=.74, PUMP'D 3523 BBLS SLK WTR W/ 121579# SAND W/ 5194# RESIN COAT IN TAIL. ISIP=2581#, FG=.75, AR=42.8, AP=6259#, MR=51.2, MP=7411#, NPI=85#, 25/40 CALC PERFS OPEN. PICKLED WELL SWIFN. HSM, FRACING</p>
2/17/2009	7:00 - 7:15	0.25	COMP	48		P		

ROCKIES

Operation Summary Report

Well: NBU 922-32CT			Spud Conductor: 12/2/2008			Spud Date: 12/18/2008		
Project: UTAH			Site: UINTAH			Rig Name No: KEY 243/243		
Event: COMPLETION			Start Date: 2/12/2009			End Date:		
Active Datum: RKB @5,043.00ft (above Mean Sea Level)			UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation
	7:15 - 17:00	9.75	COMP	36	E	P		STG #5] OPEN WELL P/U RIH W/ BKR 8K CBP & PERF GUN, SET CBP @ 8451', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90* PH, 8415'-8421' 24 HOLES, 8362'-8364' 8 HOLES, 8302'-8304' 8 HOLES [40 HOLES] WHP=2000#, INJT PSI=4850#, INJT RT=50.9, ISIP=2109#, FG=.70, PUMP'D 3135 BBLS SLK WTR W/ 124715# SAND W/ 5005# RESIN COAT IN TAIL, ISIP=2506#, FG=.74, AR=51, AP=4424#, MR=51.4, MP=5504#, NPI=397#, 30/40 CALC PERFS OPEN. STG #6] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 8171', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90* PH, 8135'-8141' 24 HOLES, 8076'-8080' 16 HOLES [40 HOLES] WHP=500#, INJT PSI=4000#, INJT RT=44.7, ISIP=2190#, FG=.71, PUMP'D 1531.3 BBLS SLK WTR W/ # SAND W/ 5300# RESIN COAT IN TAIL, ISIP=2587#, FG=.76, AR=49.9, AP=4021#, MR=50.1, MP=4461#, NPI=397#, 40/40 CALC PERFS OPEN. STG #7] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 7798', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90* PH, 7762'-7768' 24 HOLES, 7706'-7710' 16 HOLES [40 HOLES] WHP=0#, BRK DN PERFS @ 3212#, INJT PSI=5025#, INJT RT=50.2, ISIP=1976#, FG=.70, PUMP'D 1033.4 BBLS SLK WTR W/ 38332# SAND W/ 5430# RESIN COAT IN TAIL, ISIP=2477#, FG=.76, AR=50.8, AP=4381#, MR=51.1, MP=5480#, NPI=501#, 33/40 CALC PERFS OPEN. STG #8] P/U RIH W/ BKR 8K CBP & PERF GUN, SET CBP @ 7570', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90* PH, 7535'-7540' 20 HOLES, 7475'-7480' 20 HOLES [40 HOLES] WHP=0#, BRK DN PERFS @ 3128#, INJT PSI=3770#, INJT RT=50.4, ISIP=1743#, FG=.68, PUMP'D BBLS SLK WTR W/ # SAND W/ # RESIN COAT IN TAIL, ISIP=#, FG=., AR=., AP=#, MR=., MP=#, NPI=#, 40/40 CALC PERFS OPEN. P/U RIH W/ BKR 8K CBP & SET @ 7425' POOH R/D CUTTERS WIRE LINE & WEATHERFORD FRAC EQUIP. N/D FRAC VALVES, N/U BOPS, P/U 3-7/8 BIT W/ POBS, RIH W/ 2-3/8 TBG TO 7425' P/U PWR SWVL READY TO DRL IN A.M SWIFN. HSM, DRLG PLUGS
2/18/2009	7:00 - 7:15	0.25	COMP	48		P		

ROCKIES

Operation Summary Report

Well: NBU 922-32CT	Spud Conductor: 12/2/2008	Spud Date: 12/18/2008
Project: UTAH	Site: UINTAH	Rig Name No: KEY 243/243
Event: COMPLETION	Start Date: 2/12/2009	End Date:
Active Datum: RKB @5,043.00ft (above Mean Sea Level)	UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation
	7:15 - 18:00	10.75	COMP	44	C	P		<p>OPEN WELL 0# SITP, 0# SICP, EST CIRC W/ RIG PUMP,</p> <p>PLUG #1] DRL THROUGH BKR 8K CBP @ 7426' IN 10 MIN. 300# INCREASE.</p> <p>PLUG #2] CONTINUE TO RIH TAG SAND @ 7540' [33' FILL] C/O & DRL THROUGH BKR 8K CBP @ 7570' IN 10 MIN. 300# INCREASE.</p> <p>PLUG #3] CONTINUE TO RIH TAG SAND @ 7762' [36' FILL] C/O & DRL THROUGH BKR 8K CBP @ 7798' IN 10 MIN. 800# INCREASE.</p> <p>PLUG #4] CONTINUE TO RIH TAG SAND @ 8140' [30' FILL] C/O & DRL THROUGH BKR 8K CBP @ 8171' IN 10 MIN. 600# INCREASE.</p> <p>PLUG #5] CONTINUE TO RIH TAG SAND @ 8364' [97' FILL] C/O & DRL THROUGH BKR 8K CBP @ 8461' IN 10 MIN. 200# INCREASE.</p> <p>PLUG #6] CONTINUE TO RIH TAG SAND @ 8616' [30' FILL] C/O & DRL THROUGH BKR 8K CBP @ 8646' IN 10 MIN. 200# INCREASE.</p> <p>PLUG #7] CONTINUE TO RIH TAG SAND @ 8736' [30' FILL] C/O & DRL THROUGH BKR 8K CBP @ 8766' IN 10 MIN. 300# INCREASE.</p> <p>PLUG #8] CONTINUE TO RIH TAG SAND @ 8860' [140' FILL] C/O DRL THROUGH BKR 8K CBP @ 9000' IN 10 MIN. 100# INCREASE.</p> <p>CONTINUE TO RIH & C/O TO PBTD @ 9219' CIRC HOLE, R/D PWR SWVL, L/D 23 JNTS ON FLOAT, P/U HANGER & LAND W/ 286 JNTS 2-3/8 J-55 TBG, EOT @ 8801.41, R/D TBG EQUIP, N/D BOPS, N/U WELL HEAD, DROP BALL PUMP OFF BIT @ 2300#, TURN WELL OVER TO FLOW BACK CREW. LEFT SHUT IN FOR 30 MIN BEFORE FLOWING BACK.</p>
2/19/2009	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2400#, TP 2150#, 20/64" CK, 60 BWPH, - SAND, - GAS</p> <p>TTL BBLS RECOVERED: 4755</p> <p>BBLS LEFT TO RECOVER: 11300</p>
2/20/2009	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 3200#, TP 2350#, 20/64" CK, 55 BWPH, - SAND, - GAS</p> <p>TTL BBLS RECOVERED: 5190</p> <p>BBLS LEFT TO RECOVER: 9910</p>
2/21/2009	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 3400#, TP 2500#, 18/64" CK, 25 BWPH, TRACE SAND, - GAS</p> <p>TTL BBLS RECOVERED: 5998</p> <p>BBLS LEFT TO RECOVER: 9102</p>
2/22/2009	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 3100#, TP 2300#, 20/64" CK, 20 BWPH, - SAND, - GAS</p> <p>TTL BBLS RECOVERED: 6548</p> <p>BBLS LEFT TO RECOVER: 8552</p>

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22649
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		7. UNIT OR CA AGREEMENT NAME UNIT #891008900A
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078		8. WELL NAME AND NUMBER: NBU 922-32CT
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 809'FNL, 2154'FWL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:		9. API NUMBER: 4304740133
PHONE NUMBER: (435) 781-7024		10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES
11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 32 9S, 22E		12. COUNTY UINTAH
		13. STATE UTAH

14. DATE SPUDDED: 12/2/2008	15. DATE T.D. REACHED: 1/11/2009	16. DATE COMPLETED: 2/20/2009	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 5025'GL
18. TOTAL DEPTH: MD 9,275 TVD	19. PLUG BACK T.D.: MD 9,219 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL-CCL-GR SD, DSN, ACTR			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8 J-55	36#		2,420		700			
7 7/8"	4 1/2 I-80	11.6#		9,275		1650			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	8,801							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) MESAVERDE	7,475	9,146			7,475 9,146	0.36	320	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) WSMVD								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
7475'-9146'	PMP 15,092 BBLs SLICK H2O & 559,542# 30/50 OTTOWA SD

29. ENCLOSED ATTACHMENTS:

- ☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: _____

30. WELL STATUS:

PROD

RECEIVED

MAR 23 2009

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 2/20/2009		TEST DATE: 2/23/2009		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,520		WATER – BBL: 480		PROD. METHOD: FLOWING		
CHOKE SIZE: 18/64	TBG. PRESS. 2,450	CSG. PRESS. 3,041	API GRAVITY	BTU – GAS		GAS/OIL RATIO	24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,520		WATER – BBL: 480		INTERVAL STATUS: PROD	

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER	1,359				
BIRDS NEST	1,678				
MAHOGANY	2,153				
WASATCH	4,595	7,092			
MESAVERDE	7,107	9,238			

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 3/17/2009

This report must be submitted within 30 days of

- completing or plugging a new well
- reentering a previously plugged and abandoned well
- drilling horizontal laterals from an existing well bore
- significantly deepening an existing well bore below the previous bottom-hole depth
- recompleting to a different producing formation
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22649			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 922-32CT			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0809 FNL 2154 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 32 Township: 09.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047401330000			
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/24/2009 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Frac Factory/ Refurb Pit </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Frac Factory/ Refurb Pit
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Frac Factory/ Refurb Pit			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, LP is requesting to refurb the existing pit on this well pad for completion operations. The refurb pit will be relined per the requirements in the COA of the APD. Upon completion of the wells on this pad, Kerr-McGee is also requesting to utilize this pit as a Frac Factory staging pit to be utilized for other completion operations in the area. There will be a 2-400 bbl skim tanks placed on the location. The trucks will unload water in these tanks before the water is placed into the refurbished pit. The purpose of the skim tanks is to collect any hydro-carbons that may have been associated with the other completion operations before releasing into the pit. We plan to keep this pit open for 1 year. During this time the surrounding well location completion fluids will be recycled in this pit and utilized for other frac jobs in the area. Thank you.					
<div style="text-align: right;"> Approved by the Utah Division of Oil, Gas and Mining Date: <u>December 15, 2009</u> By: </div>					
NAME (PLEASE PRINT) Danielle Piernot	PHONE NUMBER 720 929-6156	TITLE Regulatory Analyst			
SIGNATURE N/A	DATE 11/23/2009				



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources


Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047401330000

Conditions of Approval

- 1. A synthetic liner with a minimum thickness of 30 mils with a felt subliner shall be properly installed and maintained in the pit.**

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: December 15, 2009
By: 

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22649
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 922-32CT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0809 FNL 2154 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 32 Township: 09.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047401330000
PHONE NUMBER: 720 929-6100		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/15/2015	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input type="text" value="TUBING OBSTRUCTION"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. A WORKOVER FOR TUBING OBSTRUCTION HAS BEEN COMPLETED ON THE NBU 922-32CT, SEE THE ATTACHED OPERATIONS SUMMARY REPORT.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY July 20, 2015		
NAME (PLEASE PRINT) Doreen Green	PHONE NUMBER 435 781-9758	TITLE Regulatory Analyst II
SIGNATURE N/A	DATE 7/20/2015	

US ROCKIES REGION
Operation Summary Report

Well: NBU 922-32CT				Spud Conductor: 12/2/2008				Spud date: 12/18/2008			
Project: UTAH-UINTAH				Site: NBU 922-32CT				Rig name no.: MILES 2/2			
Event: WELL WORK EXPENSE				Start date: 7/9/2015				End date: 7/15/2015			
Active datum: RKB @5,043.00usft (above Mean Sea Level)				UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0							
Date	Time Start-End		Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation		
6/30/2015	7:00 - 13:00		6.00	MAINT	35	D	P		got to location and tried to trip plunger was not able to trip ran down with JDC Equilized well to the casing pressure. Ran down and tagged plunger @8,085 came up out of the hole and got hung up @7,863 sat and tried making my way threw kept getting hung up and would come down where i was stacking out and come up slow after 45min trying to come out of where i was getting hung up was able to get past it kept getting hung up so i would come out slow and when my weight indicator would get to 850Lbs i would stop and try to let some of the scale and fluid get past. my weight would drop and i would start coming out of the hole once again. did that up to 6,200 is where my weight dropped and was weighing normal came out of well slow in case i got hung up again. Clean up plunger 1.88 had a lot of dings and dents on plunger. re build scratcher and ran down with it. hit some tight spots going down starting @1,700-1,800/3,420/3,663/4,520/6,630/6,900-7,222 /7,580-7,832/8,143 stacked out and beat my way down to 8,175 sat and beat for about one hour and made it to 7,178 beat down from that depth to 8,180 for about one hour came out of hole and blew well down. as well was blowing i pulled line and tied new rope socket. kept checking well to see if it would unload and was not unloading blew well for about one hour and a half rig down and called John Young to see what he wanted me to do. left plunger on well head and kicked well to sales. called pumper to let him know what i did to the well and parked wireline truck at savage yard.		
7/9/2015	7:00	- 7:30	0.50	MAINT			P		HSM, RIGGING DOWN & MOVEING EQUIP.		
	7:30	- 10:30	3.00	MAINT	30	A	P		RIG DOWN OFF NBU 922-2913DS, MIRU, CONTROL TBG W/ 30 BBLs CSG W/ 20 BBLs T-MAC, ND WH UNLAND TBG NOT STUCK RELAND.		
	10:30	- 11:30	1.00	MAINT	30	F	P		NU BOPS RU FLOOR & TBG EQUIP UNLAND L/D HANGER, PU 18 JTS 23/8 L-80 TAG UP @ 9163' 17' BELOW BTM PERF, L/D 18 JTS		
	11:30	- 14:30	3.00	MAINT	45	A	P		RU SCANTECH, SCAN & S.L.M OUT W/ 116 JTS 23/8 J-55,		
	14:30	- 16:00	1.50	MAINT	46	C	W		WAITING FOR LIGHTNING STORM TO BLOW OVER NEVER QUIT SWI SDFN.		
7/10/2015	7:00	- 7:30	0.50		48		P		HSM, PULLING WET TRIP & WATCHING FOR TOOLS STUCK IN TBG.		

US ROCKIES REGION
Operation Summary Report

Well: NBU 922-32CT		Spud Conductor: 12/2/2008		Spud date: 12/18/2008	
Project: UTAH-UINTAH		Site: NBU 922-32CT			Rig name no.: MILES 2/2
Event: WELL WORK EXPENSE		Start date: 7/9/2015		End date: 7/15/2015	
Active datum: RKB @5,043.00usft (above Mean Sea Level)			UWI: 0/9/S/22/E/32/0/NENW/6/PM/N/809.00/W/0/2,154.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
	7:30 - 10:30	3.00	MAINT	45	A	P		SICP 450, SITP 0, OPEN CSG TO FB TNK, SCAN OUT W/ REM 160 JTS 23/8 J-55 WET TBG PLUGGED, TOTAL OF 276 JTS, YB 111, BB 48, RED 117, LAST JT HAD SPRING IN X/N FISH NECK WAS GONE, HEAVEY EXT PITTING & WALL LOSS JTS 9-160, HOLE IN JT 81, HEAVEY EXT PITTING JTS 85-94, HEAVEY PITTING IN PINS JTS 30-38, MED EXT SCALE JTS 251-263, HEAVY EXT SCALE JTS 264-276, HEAVY INT SCALE JTS 250-276.
	10:30 - 15:00	4.50	MAINT	31	I	P		RD NSCAN TECH, RIH W/ 37/8 SLUAGH MILL & 159 JTS 23/8 J-55 FROM WELL, 6' L-80 PUP JT, 3 JTS 23/8 P-110 EOT @ 5015', JUST ABOVE TOP PERF, PREP TO C/O 7/13/15 SWI SDFWE.
7/13/2015	7:00 - 7:30	0.50	MAINT	48		P		HSM, WORKINGB W/ FOAM UNIT
	7:30 - 9:30	2.00	MAINT	31	I	P		SICP & SITP 675, OPEN CSG TO FB TNK, CONTROL TBG W/ 15 BBLS T-MAC, PU 104 JTS TOTAL 266 JTS IN TAGGED UP @ 8310', RU DRLG EQUIP INSTALLED TSF, BROKE CIRC W/ AIR/FOAM IN 1 HR 10 MIN.
	9:30 - 17:00	7.50	MAINT	44	D	P		C/O HARD SCALE F/ 8310' TO 8955' CIRC CLN, KILL TBG, POOH 20 JTS REM TSF, RIH 20 JTS INST TSF, SWI SDFN.
7/14/2015	7:00 - 7:30	0.50	MAINT	48		P		HSM, WORKING W/ FOAM INIT & POWER SWIVEL.
	7:30 - 10:30	3.00	MAINT	44	D	P		SICP 700, OPEN CSG TO FB TNK, BROKE CIRC W/ AIR/FOAM, C/O HARD SCALE F/ 8955' TO 9146' SAND F/ 9146' TO 9210' PBTD @ 9219', CIRC CLN, KILL TBG, RD SWIVEL.
	10:30 - 17:00	6.50	MAINT	31	I	P		L/D 8 JTS REM TSF, L/D 11 JTS. POOH W/ 116 JTS 23/8 P-110, 6' L-80 PUP JT, 159 JTS 23/8 J-55 L/D MILL. PU RIH W/ 1.875 X/N & 215 JTS 23/8, BROACHING EOT @ 6704' SWI SDFN.
7/15/2015	7:00 - 7:30	0.50	MAINT	48		P		HSM, BROACHING TBG W/ SAND LINE.
	7:30 - 15:00	7.50	MAINT	31	I	P		SICP & SITP 600 PSI, OPEN CSG TO FB TNK, CONTROL TBG W/ 20 BBLS T-MAC, RIH W/ REM 60 JTS 23/8 P-110 BROACHING, LAND TBG, ND BOPS, NU WH SWI FOR BUILD UP, WELL WAS CLEANED OUT W/ AIR/FOAM WILL NEED TO BE PURGE BEFORE START UP. RDMOL TO CLOSE BY NBU 1022-4H PAD PREP TO MIRU 7/16/15, SDFD K-B = 18' HANGER = .83' 116 JTS 23/8 P-110 = 3685.56' PUP JT L-80 = 6.09' 159 JTS 23/8 J-55 = 4902.13' X/N 1.875 = 1.05' EOT @ 8613.66' TWLTR 80 BBLS